

---

**ADA COMPLIANCE REPORT FOR  
WARREN COUNTY  
MCMINNVILLE, TENNESSEE**




---

DATE: 7/20/17

PROJECT NO. 1704

**UPLAND DESIGN GROUP, INC.**



P.O. Box 1026  
Crossville, TN 38557  
Phone: 931-484-7541  
Fax: 931-484-2351  
[www.uplanddesigngroup.com](http://www.uplanddesigngroup.com)

## Table of Contents

Section 1	Executive Summary
Section 2	Airport Terminal Building
Section 3	Animal Shelter Building
Section 4	Courthouse Building
Section 5	Courthouse Annex Building
Section 6	EMS Billing Office Building
Section 7	Health Department Building
Section 8	Highway Department Building
Section 9	Sheriff's Office Building
Section 10	Temporary Morgue Building
Section 11	Sanitation Recycling & Convenience Center
Section 12	Fairgrounds
Section 13	Probable Cost Summary

Section Divider

(Left Blank Intentionally)



## EXECUTIVE SUMMARY

The following information in this report is to aid with a transition plan for Warren County to make the following facilities ADA complaint under Title II – 28 CFR 35.150. With this information, Warren County, can develop a self-evaluation plan, establish a schedule and budget to implement the transition plan.

The information gathered for each facility was based on site observations and field measurements. The costs are based on today's dollars and do not reflect inflation, interest rates, etc. Each renovation, addition and/or corrective measure reflects the current needs and goals of each facility.

Cost estimates are based on a single General Contractor bidding and performing all work under a single contract.

Section Divider

(Left Blank Intentionally)



**Warren County Airport Terminal Building**

Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	H/C Parking	Provide new pavement markings to provide 8'-0" wide H/C parking stalls and 8'-0" access isle – See drawing A1.1	\$400	
2	H/C Parking	Provide a H/C parking sign – See drawing A1.1	\$100	
3	H/C Parking	Provide tactile warning on existing ramp – See drawing A1.1	\$300	
4	Entrance Door	Add power access ADA push button access controls to front door Exterior push plate switch should be located on a pedestal, while the interior located the latch of the door on an existing wall	\$3000	
5	Men RR	Replace existing toilet partitions with new – See drawing A1.2	\$3000	
6	Men RR	Lavatory Countertop needs to be raised to 34" AFF; Replace faucet controls with H/C style; Provide insulation on all exposed piping under counter – See drawing A1.2	\$600	
7	Men RR	The clearance on the pull side of the door is not with ADA requirements. Not feasible to correct.	NA	
8	Women RR	Replace existing toilet partitions with new – See drawing A1.2	\$3000	
9	Women RR	Lavatory Countertop needs to be raised to 34" AFF; Replace faucet controls with H/C style; Provide insulation on all exposed piping under counter – See drawing A1.2	\$600	
10	Women RR	The clearance on the pull side of the door is not with ADA requirements. Not feasible to correct.	NA	
11	Drinking Fountain	Lower so that spout is 36" max AFF	\$300	
		Probable Cost	\$11,300	


**Warren County Airport Terminal Building**




Items 1, 2 and 3



Item 4




Items 5 and 8




Item 6




Item 7



Item 9




Item 10




**HC PARKING SIGN**  
NOT TO SCALE

2




**SITE PLAN**

NOTE:  
SYMBOL TO BE PAINTED ON ALL HANDICAP SPACES W/ 2 COATS OF WHITE TRAFFIC PAINT AND BACKGROUND BOX TO BE PAINTED W/ 2 COATS OF BLUE TRAFFIC PAINT




**HC SYMBOL DETAIL**  
NOT TO SCALE

1




WARREN COUNTY AIRPORT  
WARREN COUNTY ADA  
FACILITIES STUDY

REFERENCED DRAWING  
**A1.1**  
DATE  
**07/20/17**



## PUBLIC RESTROOMS



WARREN COUNTY AIRPORT  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING

A1.2

DATE

07/20/17

Section Divider

(Left Blank Intentionally)

**Warren County Animal Shelter**

Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	H/C Parking	Provide a new H/C parking space with proper access isle - See drawing A2.1	\$5,000	
2	H/C Parking	Provide accessible pathway to front door from H/C parking – See drawing A2.1	\$1,000	
3	H/C Parking	Provide a H/C parking sign – See drawings A2.1	\$100	
4	Screen Door	Replace screen door with new half screen door that has ADA accessible handle and closer	\$200	
5	Front Entrance Door	Replace existing knob lockset with lever handle lockset; Replace existing non-H/C threshold with a H/C threshold	\$120	
6	Interior Doorway	Replace existing non-H/C threshold with a H/C threshold	\$150	
		Probable Cost	\$6,570	



Items 1, 2 and 3





Item 4



Item 6



Item 5




NOTE:  
 SYMBOL TO BE PAINTED ON ALL  
 HANDICAP SPACES W/ 2 COATS  
 OF WHITE TRAFFIC PAINT AND  
 BACKGROUND BOX TO BE  
 PAINTED W/ 2 COATS OF BLUE  
 TRAFFIC PAINT

HC SYMBOL DETAIL

NOT TO SCALE

1



HC PARKING SIGN

NOT TO SCALE

2



WARREN COUNTY ANIMAL SHELTER  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING

A2.1

DATE

07/20/17

Section Divider

(Left Blank Intentionally)



**Warren County Courthouse**


<b>Item #</b>	<b>Area of Work</b>	<b>Description of Work</b>	<b>Estimated Cost</b>	<b>Work Completed</b>
1	Entrance Door	Add power access ADA push button access controls to front door Both interior and exterior push plate switches to be located on the latch of the door on an existing wall	\$3,000	
2	Drinking Fountains	The 3 drinking fountains throughout the building need to be replaced with ADA compliant – See drawings A3.1 and A3.2	\$2,500	
3	Circuit Court Clerk Office	Change door hardware to lever handle at both set of doors	\$300	
4	Circuit Court Clerk Office	Add H/C counter to the public counter by using the existing lift counter and modifying the counter in that area – See drawing A3.3	\$400	
5	Circuit Court Clerk Office	Add H/C counter to the Lawyer counter by modifying the counter near the swing gate – See Drawing A3.3	\$1,100	
6	H/C Restroom – First Floor	Neither of the existing Public Restrooms are feasible to be renovated for H/C accessibility. It has been determined to renovate one of the Staff Restrooms into a new Unisex H/C Restroom – See drawing A3.4	\$8,000	
7	H/C Restroom – Second Floor	Neither of the existing Public Restrooms are feasible to be renovated for H/C accessibility. It has been determined to renovate one of the Jury's Restrooms into a new Unisex H/C Restroom – See drawing A3.5	\$4,500	
8	General Session Court Room	There is an existing ramp within this room, but there is no landing at head of the ramp. Provide a new wall and door approx. 5 feet into hallway – See drawings A3.6	\$4,000	
9	Jury Room	Change door hardware to lever handle	\$200	

**Warren County Courthouse**

Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
10	Circuit Court Courtroom	The ramp to the Jury Box is too steep, per Warren County Circuit Court Secretary (Judicial ADA Coordinator for Warren and Van Buren County) a jury in a wheel chair sits outside of the jury box on the floor behind the Plaintiff's table Make the Jury box accessible by providing a proper sloped ramp behind the Plaintiff's Table	\$3,000	
11	Circuit Court Courtroom	The Gallery is a sloped floor and has no level area for wheel chairs. Per Warren County Circuit Court Secretary (Judicial ADA Coordinator for Warren and Van Buren County) an individual who is in a wheel chair sits outside of the gallery on the floor adjacent to the Defendants table. No work is required for this area if all parties are in agreement that this is acceptable. If not provide wood privacy wall	NA	
12	Circuit Court Courtroom	Judges bench area with includes Clerk and Witness stand is not accessible. Provide a ADA wheelchair lift, since there is not enough room to provide a ramp to each separate level.	NA	
Probable Cost			\$27,000	




Item 1



Item 2



**Warren County Courthouse**




Item 4




Item 8



Item 10




Item 11



Item 12

SEE DRAWING - A3.4

SEE DRAWING - A3.5



### FIRST FLOOR



## WARREN COUNTY COURTHOUSE WARREN COUNTY ADA FACILITIES STUDY

REFERENCED DRAWING


# A3.1

DATE

## 07/20/17


SEE DRAWING - A3.5

DRINK FOUNTAIN TO BE REPLACED



SEE DRAWING - A3.6

### SECOND FLOOR



## WARREN COUNTY COURTHOUSE WARREN COUNTY ADA FACILITIES STUDY

REFERENCED DRAWING  
**A3.2**  
DATE  
**07/20/17**

REDO COUNTER AND SWING GATE TO ALLOW FOR H/C COUNTER AND NEW LIFT GATE, TOP OF COUNTER AND LIFT GATE TO BE 34" AFF

CHANGE EXISTING LOCKSET TO LEVER HANDLE LOCKSET

CIRCUIT COURT CLERK OFFICE

HALLWAY

CHANGE EXISTING LOCKSET TO LEVER HANDLE LOCKSET

CIRCUIT COURT CLERK OFFICE

REDO COUNTER AND LIFT GATE TO ALLOW FOR H/C COUNTER, TOP OF COUNTER AND LIFT GATE TO BE 34" AFF

CIRCUIT COURT CLERK OFFICE




WARREN COUNTY COURTHOUSE  
WARREN COUNTY ADA  
FACILITIES STUDY

REFERENCED DRAWING

A3.3

DATE

07/20/17



UNISEX H/C CONFIGURATION - FIRST FLOOR




WARREN COUNTY COURTHOUSE  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING

A3.4

DATE

07/20/17



UNISEX H/C CONFIGURATION - SECOND FLOOR




WARREN COUNTY COURTHOUSE  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING

A3.5

DATE

07/20/17



RELOCATION OF DOOR AT GENERAL SESSIONS COURT



WARREN COUNTY COURTHOUSE  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING

A3.6

DATE

07/20/17

Section Divider

(Left Blank Intentionally)



**Warren County Courthouse Annex**

Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	Front H/C Parking	Provide H/C parking sign so bottom is 60" AFF (x4)	\$400	
2	Front H/C Parking	Mirror and re-paint H/C symbol in parking stalls (x4)	\$500	
3	Front Entrance Door	Add power access ADA push button access control. Exterior push plate switch should be located on a pedestal or on an existing column. The interior push plate to be located an existing wall, hinge side of the door	\$3,000	
4	County Trustee	Provide a 34" high table with 27" clear knee space in room and add sign at counter "PLEASE ASK FOR ASSITANCE"	\$400	
5	County Property Assessor	Provide a 34" high table with 27" clear knee space in room and add sign at counter "PLEASE ASK FOR ASSITANCE"	\$400	
6	Rear Door Entrance at 4-H & Ag Ext	Add power access ADA push button access control, locate on latch of the door on existing wall – See drawing A4.2	\$3,000	
7	H/C Parking at 4-H & Ag Extension	Provide a new 16'x 20' H/C parking space along the side of the building and stripe a walkway to the entrance door. Provide van accessible and H/C parking sign – See drawing A4.2	\$6,000	
8	County Clerk	Provide a 34" high table with 27" clear knee space in room and add sign at counter "PLEASE ASK FOR ASSITANCE"	\$400	
9	Election Commission Office	Provide a lift gate / shelf to the left side of the existing counter. Height of work surface to be 34" AFF or provide a 34" high table with 27" clear knee space in room and add sign at counter "PLEASE ASK FOR ASSITANCE"	\$400	
10	Women's RR	Modify restroom so that there is a 5'-0" turn between the door and privacy wall; modify toilet stalls so that the H/C stall is (cont)	\$7,500	



**Warren County Courthouse Annex**

		5'-0" wide clear. Install new H/C water closet so that the center line of the water closet is 18" off the side wall. Install proper grab bars 36" on back wall and 42" on side wall. Height of grab bars 34" AFF – See drawing A4.3		
11	Men's RR	Modify restroom so that there is a 5'-0" turn between the door and privacy wall; modify toilet stalls so that the H/C stall is 5'-0" wide clear. Install new H/C water closet so that the center line of the water closet is 18" off the side wall. Install proper grab bars 36" on back wall and 42" on side wall. Height of grab bars 34" AFF; lower urinal as required so that rim of urinal is 17" AFF – See Drawing A4.3	\$7,500	
12	Entrance Door to Lower Level Meeting Room	Remove existing concrete landing, concrete ramp and existing guardrail. Install new concrete landing, a 5'-6" wide ramp (1:12 slope max), new 34" wall mounted rail on building and a 34" high rail along paving side of the ramp and landing – See drawings A4.4 and A4.6	\$8,000	
13	Entrance Door to UCHRA	Remove existing concrete landing, concrete ramp and existing guardrail. Install new concrete landing, a 5'-6" wide ramp (1:12 slope max), new 34" handrail along building and a 34" high rail along paving side of the ramp and landing – See drawings A4.4 and A4.5	\$14,000	
14	H/C Parking for UCHRA	At the existing parking spaces across the drive from the UCHRA office, provide new van parking space with 8'-0" access aisle across from the new ramp. Provide pavement marking showing crossing from parking to ramp as well as H/C parking sign	\$500	

**Warren County Courthouse Annex**

15	Men's RR in UCHRA Office	Reconfigure the restroom so that it is only a H/C water closet and wall mounted sink. Relocating of the water closet must be done to meet the current ADA for clearance of 60" from side wall to side. Relocated the existing wall hung lavatory where the existing urinal is to provide clearance at the door. Replace the push pull plates, with a lever handle privacy set. The water closet is to be between 16"-18" from side wall and the lavatory rim at 34" AFF – See drawing A4.7	\$9,000	
16	Women's RR in UCHRA Office	Remove existing toilet partitions and install new so that there is a clearance of 60" from side wall to toilet partition, presently there is 50" for the H/C water closet. Confirm that water closet is between 16"-18" from side wall. Lower the existing lavatory countertop to 34" AFF – See drawing A4.7	\$5,000	
		Probable Cost	\$66,000	



Items 1 and 2



Items 1 and 2

**Warren County Courthouse Annex**



Item 3



Sample of sign for Items 4, 5, 8 & 9




Item 12




Item 13



Item 14








**HC PARKING SIGN**  
NOT TO SCALE

PROVIDE NEW POWER  
ACCESS ADA PUSH BUTTON  
CONTROLS

PAINT OUT EXISTING H/C  
SYMBOLS AND REMOVE  
EXISTING H/C PARKING  
SIGN

2





NOTE:  
SYMBOL TO BE PAINTED ON ALL  
HANDICAP SPACES W/ 2 COATS  
OF WHITE TRAFFIC PAINT AND  
BACKGROUND BOX TO BE  
PAINTED W/ 2 COATS OF BLUE  
TRAFFIC PAINT

**HC SYMBOL DETAIL**  
NOT TO SCALE


1

**NEW H/C PARKING AT LOWER LEVEL**




WARREN COUNTY COURTHOUSE ANNEX  
WARREN COUNTY ADA  
FACILITIES STUDY

REFERENCED DRAWING  
**A4.2**  
DATE  
**07/20/17**




DEMOLITION PLAN




RENOVATION PLAN

MEN'S RESTROOM AT MAIN LEVEL



DEMOLITION PLAN



RENOVATION PLAN

WOMEN'S RESTROOM AT MAIN LEVEL




WARREN COUNTY COURTHOUSE ANNEX  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING


A4.3

DATE

07/20/17




DEMOLITION PLAN




RENOVATION PLAN

ENTRANCE DOOR AT LOWER LEVEL MEETING ROOM



DEMOLITION PLAN



RENOVATION PLAN

PUBLIC ENTRANCE DOOR AT UCHRA




WARREN COUNTY COURTHOUSE ANNEX  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING

A4.4


DATE

07/20/17




**HANDRAIL ELEVATION**

NOT TO SCALE



**HANDRAIL ELEVATION**

NOT TO SCALE



**HANDRAIL ELEVATION**

NOT TO SCALE



**HANDRAIL ELEVATIONS AT PUBLIC ENTRANCE DOOR AT UCHRA**




WARREN COUNTY COURTHOUSE ANNEX  
WARREN COUNTY ADA  
FACILITIES STUDY

REFERENCED DRAWING

A4.5

DATE

07/20/17



**HANDRAIL ELEVATION**


NOT TO SCALE

1

**HANDRAIL ELEVATION**

NOT TO SCALE

2



**HANDRAIL ELEVATION**

NOT TO SCALE

3

**HANDRAIL ELEVATIONS ENTRANCE DOOR AT LOWER LEVEL MEETING ROOM**




**WARREN COUNTY COURTHOUSE ANNEX  
WARREN COUNTY ADA  
FACILITIES STUDY**

REFERENCED DRAWING


**A4.6**

DATE

**07/20/17**



DEMOLITION PLAN



RENOVATION PLAN

RESTROOM RENOVATIONS UCHRA



WARREN COUNTY COURTHOUSE ANNEX  
 WARREN COUNTY ADA  
 FACILITIES STUDY

REFERENCED DRAWING

A4.7

DATE


07/20/17

Section Divider


(Left Blank Intentionally)

**Warren County EMS Billing Office**

Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	H/C Parking	Provide a new 16'x20 H/C parking space with proper access isle – See drawing A5.1	\$7,000	
2	H/C Parking	Provide pavement markings from H/C parking to concrete stoop at front door – See drawing A5.1	\$500	
3	H/C Parking	Provide a H/C parking sign – See drawing A5.1	\$200	
4	Counter	Lower a portion of the existing counter to 30" AFF – See drawing A5.2	\$1,300	
		Probable Cost	\$9,000	




Items 1, 2 and 3



Item 4

NOTE:  
 SYMBOL TO BE PAINTED ON ALL  
 HANDICAP SPACES W/ 2 COATS  
 OF WHITE TRAFFIC PAINT AND  
 BACKGROUND BOX TO BE  
 PAINTED W/ 2 COATS OF BLUE  
 TRAFFIC PAINT



4" WIDE LINE - TYPICAL

**HC SYMBOL DETAIL**

NOT TO SCALE

1

EXISTING GRASS AREA  
 PROVIDE ASPHALT THIS AREA  
 FOR H/C PARKING  
 NEW H/C PARKING SIGN  
 NEW EXTRUDED  
 CONCRETE CURB

**MAGNESS DRIVE**

EXISTING ASPHALT DRIVE

EXISTING ASPHALT DRIVE

EXISTING ASPHALT DRIVE

NEW PAVEMENT MARKINGS

EXISTING CONCRETE STOOP

EXISTING EMS BILLING BUILDING



60"

**OMNI DRIVE**

**HC PARKING SIGN**

NOT TO SCALE

2



**Upland  
 Design  
 Group**







WARREN COUNTY - EMS BILLING OFFICE  
 WARREN COUNTY ADA  
 TRANSITION PLAN

REFERENCED DRAWING

**A5.1**

DATE

**07/20/17**



WARREN COUNTY - EMS BILLING OFFICE  
WARREN COUNTY ADA  
TRANSITION PLAN

REFERENCED DRAWING  
**A5.2**  
DATE  
**07/20/17**

Section Divider


(Left Blank Intentionally)



**Warren County Health Department**

Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	H/C Parking	Provide new pavement markings to provide 8'-0" wide H/C parking stalls and 8'-0" access isle	\$500	
2	H/C Parking	Provide an accessible pathway from H/C parking to entrance door	\$300	
3	Entrance Door	Remove existing slope concrete landing and provide new 6' wide concrete landing with a 1:20 6' wide concrete ramp. Landing shall be at the same elevation as the building. Ramp to run parallel with building. Both the landing and ramp are to be part of accessible pathway. Note: there will be a 6" step from landing to asphalt	\$5,000	
4	Entrance Door	Add power access ADA push button access controls to front door Exterior push plate switch should be located on a pedestal, while the interior located the latch of the door on an existing wall. Power access controls will control the exterior door and the interior door of the airlock together	\$3,000	
5	Entrance Door	Existing door is a pair of 30" wide leaves. Remove existing and provide a new 36" wide door with sidelite	\$5,000	
6	AirLock Door	Existing door is a pair of 30" wide leaves. Remove existing and provide a new 36" wide door with sidelite	\$5,000	
7	Handicap Restroom	Provide new ADA toilet seat riser. Top of toilet seat to be 17" – 19" AFF	\$100	
8	Handicap Restroom	Remove 24" long grab bar on the back and install new 36" long mounted 34" AFF.	\$300	
9	Handicap Restroom	Door hardware to be replaced with a ADA accessible lever handle privacy set	\$200	
10	Handicap Restroom	Relocate the restroom door signage is to be located on the wall on the latch side of the door rather than on the door	\$100	
		Probable Cost	\$17,500	

**Warren County Health Department**



Item 1




Item 2




Items 3, 4 and 5



Item 6



Items 7 and 8




Items 9 and 10

Section Divider


(Left Blank Intentionally)

**Warren County Highway Building**


Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	H/C Parking	Provide new pavement markings to provide 16' x 20' H/C parking and access isle – See drawing A7.1	\$5,000	
2	Front Door	Add power access ADA push button access controls to front door Both interior and exterior push plate switches to be located the latch of the door on an existing wall	\$3,000	
3	Restrooms	Add sign in lobby "NO PUBLIC RESTROOMS"	\$100	
4	Counter	Add sign at counter "PLEASE ASK FOR ASSITANCE"	\$100	
		Probable Cost	\$8,200	



Item 1



Item 2



Items 3 and 4



Sample of sign for Item 4




Section Divider

(Left Blank Intentionally)

**Warren County Sheriff's Office**


Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	H/C Parking	Provide new pavement markings to provide (1) 8'-0" wide H/C parking stall and 8'-0" access isle. Provide new pavement marking on remaining parking. Note: loose the other H/C parking, but widen the other parking stalls – See drawing A8.1	\$600	
2	H/C Parking	Raise H/C parking sign so bottom is 84" AFF	\$300	
3	H/C Parking	Provide tactile warning on existing ramp	\$400	
4	Men RR	Add a 36" long grab bar behind the water closet. Grab bar to be mounted 34" AFF	\$400	
5	Men RR	Existing center of water closet is 15 ½", provide an offset flange so the center of water closet is to be between 16"-18" from side wall	\$2,000	
6	Women RR	Add a 36" long grab bar behind the water closet. Grab bar to be mounted 34" AFF	\$400	
7	Women RR	Existing center of water closet is 18 ½", provide an offset flange so the center of water closet is to be between 16"-18" from side wall	\$2,000	
		Probable Cost	\$5,700	



Items 1, 2 and 3



Items 4 - 7




RAISE EXISTING H/C SIGN SO THAT BOTTOM OF SIGN IS 84"

NEW SURFACE MOUNTED TACTICAL WARNING SURFACE

RE-STRIPING OF EXISTING TO ALLOW ACCESS AISLE TO BE WIDEN TO 8'-0" BETWEEN 8'-0" PARKING STALLS


NOTE:  
SYMBOL TO BE PAINTED ON ALL HANDICAP SPACES W/ 2 COATS OF WHITE TRAFFIC PAINT AND BACKGROUND BOX TO BE PAINTED W/ 2 COATS OF BLUE TRAFFIC PAINT



HC SYMBOL DETAIL

NOT TO SCALE

1



HC PARKING SIGN

NOT TO SCALE

2



WARREN COUNTY SHERIFF'S OFFICE  
WARREN COUNTY ADA  
FACILITIES STUDY

REFERENCED DRAWING

A8.1

DATE

07/20/17


Section Divider

(Left Blank Intentionally)




**Warren County Temporary Morgue**


Item #	Area of Work	Description of Work	Estimated Cost	Work Completed
1	H/C Parking	Provide a new 16'x20' concrete H/C parking space and access isle - See drawing A9.1	\$6,000	
		Probable Cost	\$6,000	



Item 1



NOTE:  
 SYMBOL TO BE PAINTED ON ALL  
 HANDICAP SPACES W/ 2 COATS  
 OF WHITE TRAFFIC PAINT AND  
 BACKGROUND BOX TO BE  
 PAINTED W/ 2 COATS OF BLUE  
 TRAFFIC PAINT




4" WIDE LINE - TYPICAL

**HC SYMBOL DETAIL**

NOT TO SCALE

1



**WARREN COUNTY TEMPORARY MORGUE  
 WARREN COUNTY ADA  
 FACILITIES STUDY**

REFERENCED DRAWING

**A9.1**

DATE

**07/20/17**

Section Divider

(Left Blank Intentionally)

**Warren County Sanitation Convenience Center**

<b>Item #</b>	<b>Area of Work</b>	<b>Description of Work</b>	<b>Estimated Cost</b>	<b>Work Completed</b>
1	Main Roadways	Provide signage directing visitors to the assisted drop-off locations	\$300	
2	Entrance	Install new rolling gates implementing new one way flow making sidetracking a vehicle more efficient.	\$3,500	
3	Collection Center Roll-offs	Personnel strategically located at rubbish and cardboard recycling stations	NA	
4	Community Communications	Publish collection Center modifications in local newspaper informing community of changes and ability to assist mobility challenged with their household rubbish.	\$100	
5	Access Roadway	Provide asphalt covering to rock base serving as drive to the paved collection container locations	\$6,000	Target 2020

Section Divider

(Left Blank Intentionally)

**Warren County Fairgrounds**

<b>Item #</b>	<b>Area of Work</b>	<b>Description of Work</b>	<b>Estimated Cost</b>	<b>Work Completed</b>
1	Main Roadways	Provide temporary signage directing visitors to wheelchair accessible parking areas	\$300	Targeted 7/31/2020
2	Wheelchair Parking	Modify current handicapped paved parking area to become completely wheelchair accessible (Van) parking	\$200	On-going
3	Wheelchair Parking	Increase assisted pick up and delivery to wheelchair required personnel when designated parking area is exceeded	NA	On-going
4	Handicapped Parking	Implement increased handicapped parking near food booth paved areas	TBD	Targeted 2020-2025
5	Handicapped Parking	Provide drop-off location directly on to paved walkway around grandstand area	\$1,500	Targeted 2020
6	Wheelchair Parking	Evaluate success of signage efforts in 2020 and provide additional wheelchair accessible spots in close proximity to current wheelchair accessible parking area	TBD	Targeted 2020-2025
7	Accessibility Mapping	Modify existing hand-out provided to handicapped citizens on locations of accessible parking, restrooms, eating areas, etc.	\$100	Targeted 2020

Section Divider

(Left Blank Intentionally)



### Probable Cost Summary

• Airport Terminal Building	\$ 11,300
• Animal Shelter Building	\$ 6,570
• Courthouse Building	\$ 27,000
• Courthouse Annex Building	\$ 66,000
• EMS Billing Office Building	\$ 9,000
• Health Department Building	\$ 17,500
• Highway Department Building	\$ 8,200
• Sheriff's Office Building	\$ 5,700
• Temporary Morgue Building	<u>\$ 6,000</u>
<b>Subtotal</b>	<b>\$ 157,270</b>
• Contingency 25%	\$ 39,318
• Overhead Profit 15%	<u>\$ 29,488</u>
<b>Probable Construction Cost</b>	<b>\$ 226,076</b>
A/E Fees for Report	\$ 10,000
A/E estimated Fee for Construction Document	<u>\$ 12,000</u>
<b>Probable Overall Project Cost</b>	<b>\$ 248,076</b>

