

Specs :

- Trane, or equivalent, 7.5 Ton split HVAC unit.
- Trane, or equivalent, 5 ton split HVAC unit.
- Trane, or equivalent, 4 ton split HVAC unit.

Scope of Work:

- Proper lockout/tagout will be performed on all energy.
- Remove all three units furnace, coils, and condensers.
- Remove all existing refrigerant lines and electrical from disconnect to condensers.
- Install new furnace and coils in place and tie into the existing duct with new duct fittings if required.
- Set new condensers on the pad where the old unit was set.
- Run new refrigerant lines from condenser to evaporator coils.
- Install new electrical from disconnect to the condensers.
- Install new wifi thermostats on all three units.
- Pressure test entire system and pull proper vacuum.
- Charge system and perform factory authorized start up on system.